REQUEST FOR PROPOSAL

MATERIAL PROCUREMENT FOR FIBER OPTIC NETWORK DEPLOYMENT

COLORADO RIVER INDIAN TRIBES

ADDENDUM 1

DATE: November 16, 2026

ISSUED BY:

Colorado River Indian Tribes

Tribal Council

26600 Mohave Rd.

Parker, AZ 85344

Colorado River Indian Tribes

Materials Procurement for Fiber Optic Network Deployment
Request for Proposals

ADDENDUM 1

DATE: November 16, 2026

NOTE: PROPOSER SHALL ACKNOWLEDGE RECEIPT OF ADDENDUM 1 IN THE COVER LETTER OF THE PROPOSAL.

Part 1. Answers to the Questions received prior to the deadline of November 10, 2026.

Question 1: What is the DC load of the active equipment within the cabinet? Cabinet specifications are located on page 13 of the material specifications. Per the specs, the cabinet shall include the specified -48 VDC rectifier system with dual 1,000-watt rectifier modules. Active equipment has not been determined at this time to provide accurate load requirements. Active equipment will be purchased at a later date. Supplemental equipment at the time of installation will be determined by the contract based on the active equipment needs and preferences from the network operator.

Question 2: Is Appendix A a firm list of products and quantities CRIT plans to purchase, or is it an early estimate? Appendix A, has been updated and revised bill of materials has been attached to the bid solicitation.

Question 3: Will material delivery be accepted as soon as available, or is there an expected delivery schedule? Yes, in coordinating delivery with the tribe, materials will be accepted as soon as available pending there is secured storage yard available. Final procurement schedule will be coordinated and approved by the tribe.

Question 4: What is the expected delivery address for the materials? The tribe will provide the final delivery address once the storage site is secured.

Question 5: Which materials must comply with BABA? Is there a list, or must all items be BABA compliant? All materials should be complaint to BABA where the federal requirements apply. Any exception, substitution, or waiver must be approved in writing by CRIT and the applicable funding agency before a noncompliant product is supplied.

Question 6: Can CRIT provide component breakdowns for PM2A, BM82, PE1-3, and PE2-3 assemblies? Please refer the Appendix B: Material Specifications for the material requirements of each item.

Question 7: Should bidders separately quote tracer wire, pull tape, marker posts, warning tape, conduit plugs, and couplers? Per the material specifications, “All conduit materials shall be accompanied by warning tape, pull tape, and tracer wire”. The unit price and extended price of the conduit installation shall include said items and not be quoted separately during the bid process.

Question 8: Can the UL 651A requirement for HDPE conduit be removed in favor of SDR 11? No. Appendix B requires HDPE conduit to be SDR 11 or better and compliant with ASTM F2160 and UL 651A.

Question 9: In the materials list, line item 63: BFO-1 DROP. The other BFO and CO cables display a length, but this one does not. Instead, it lists a qty requirement of 2,206. Can you please confirm what is needed for this item? Is it a pre-terminated cable like the others, or are you in need of some bulk 1 strand fiber? The revised bill of materials have been uploaded to the bid solicitation showing the CO-1 and BFO-1 items as unit of each.

Part 2. Revisions to Appendix A: Vendor Bid Sheet

A revised Appendix A: Vendor Bid Sheet dated “October 2026 – Revision 1” has been uploaded to the bid portal. Please reference this

Part 3. Revisions to the Bid Opening Location

The bid opening location shall take place at the **Bluewater Resort and Casino in Parker Arizona**. The meeting room is the **Navajo room**. The address of the casino is 11300 Resort Dr, Parker, AZ 85344.

All other conditions apply in the original package.